

Receipt for approval :-

MAHARASHTRA FILM, STAGE & CULTURAL DEVELOPMENT CORPORATION LTD.,
DADASAHEB PHALKE CHITRANAGARI, GOREGAON (EAST), MUMBAI 400 065

Quotation

Sealed percentage rate quotations are invited from experienced contractors for **Providing and fixing of galvanised Iron Sheet Fencing of periphery area of shivshahi location in Filmcity**. The details of work are as below:-

Name of the work : Providing and fixing of galvanised Iron Sheet Fencing of periphery area of shiv shahi location in Filmcity
Estimated Cost : 6,72,797.00/-
Last date of receipt of quotation : 31/03/2023 up to 4.30 pm
Date of opening of quotation : 03/04/2023 at 3.00 pm (if possible)

The blank quotations can be obtained from the office of Dy. Engineer (Civil), Maharashtra Film, Stage and Cultural Development Corporation Ltd., Dadasaheb Phalke Chitranagari, Goregaon (East), Mumbai 400 065 on all working days.

The Managing Director, M.F.S. & C.D.C. Ltd., Filmcity reserves the right to accept any tender or reject lowest or any other tender or all tenders without assigning any reason whatsoever.


Copy issued to: M/s. _____

Dy. Engineer (Civil)

QUOTATION

NAME OF WORK : Providing and fixing of galvanised Iron sheet Fencing of periphery area of shivshahi location in Filmcity.

| Sr No | Description of item | Quantity | Rate | Unit | Amount |
|------------------|---|----------|---------|------------|-------------|
| 1 | Excavation for foundation in Hard rock by chiselling, wedging, line drilling, etc.including trimming and levelling the bed, removing the excavated material upto adistance of 50 metres beyond the building area stacking as directed, dewatering and back filling with available earth/ murum watering, rramming etc.complete.(Lift up to 1.5m).By Mechanical Means | 17.00 | 1372.35 | m3 | 23329.95 |
| 2 | Providing and laying Cast in situ/ Ready Mix cement concrete M-25 of trap/ granite/ quartzite/ gneiss metal for R.C.C. work in foundations like raft, strip foundations, grill age and footings of R.C.C. columns and steel stanchions etc. including bailing out water, Steel centering, formwork, cover blocks, laying/ pumping, compaction and curing roughening the surface if special finish is to be provided (Excluding reinforcement and structural steel) etc. complete, with fully automatic micro processor based PLC with SCADA enabled reversible Drum Type mixer/ concrete Batch mix plant (Pan mixer)etc. complete. With fine aggregate (Crushed sand VSI Grade) | 17.00 | 7651.35 | m3 | 130072.95 |
| 3 | Providin gand fabricating structural steel work in rolled sections like joists, channels, angles, tees etc. as per detailed design and drawings or as directed including cutting, fabricating, hoisting, erecting, fixing in position making riveted/ bolted/ welded connections with out connecting plates, braces etc. and including one coat of anticorrosive paint and over it two coats of oil painting of approved quality and shade etc. complete. | 2.912 | 106936 | MT | 311398.21 |
| 4 | Providing and fixing corrugated galvanised iron sheets of 0.63 mm thick (24 B.W.G.) for roofing with out wind tiles including fastening with galvanised iron screws and bolts, lead and bitumen washers as per drawing etc.complete.(Weight of 5.5 Kilogram/sq.m.). | 180.00 | 913.5 | m2 | 164430.00 |
| 5 | Misc. gate fitting (hinges padder 10, stopper 2 , handrof, lock 6 , ring 12 nos etc including all. | 1.00 | 15000 | Job | 15000.00 |
| 6 | hinges for gate | 10.00 | 1500 | NO | 15000.00 |
| 7 | supplying labour for Miscellaneous work (Helper Un Skilled). | 10.00 | 645.75 | per person | 6457.50 |
| 8 | supplying welder / driller | 10.00 | 710.85 | per person | 7108.50 |
| Total Amount Rs. | | | | | 672797.11 |
| Say . | | | | | 6,72,797.00 |



Deputy Engineer (C)
Filmcity, Goregaon

I herewith quoted.....% above/ below / at par of estimated cost. The contractor can claim GST in their bill. However, the same would be reimbursed to them only if they produce the GST payment challan.

CONTRACTOR SIGN